

DAULAT RAM COLLEGE HOSTEL
UNIVERSITY OF DELHI

DRC/2024/12

Dated:26/07/2024

NOTICE INVITING QUOTATION
(CIVIL WORK)

Sealed Quotations are hereby invited from experienced contractors for making Ramp and miscellaneous work in the College Hostel.

Sealed quotations for the above mentioned civil work, address to the undersigned should be dropped into the sealed box for receiving the quotations kept at Dispatch Section, in the College Hostel Administration office of this College on any working day till 02nd August 2024 during Office Hours (9:00 am – 5:00 pm). The sealed box containing sealed quotations and the sealed quotations shall be opened in the presence of the persons offering the said quotations and / or their representatives and the members of the Concerned committee of this college at 11.00am on 05th August, 2024 in the Hostel Office.

Normally, the lowest quotations will be eligible for award of the job contracts but the concerned College committee reserves the right to award the job contracts to nearer higher-value quotations at its own discretion.

A Security Money Deposit of Rs.10,000/- (Rupees Ten thousand only) for job contract shall have to be deposited to the undersigned after award of the work, which will be refunded on satisfactory completion of the job contracts.

On completion of 50% of the job within 30 days from the date of the work order received by the concerned contractor, a payment of 50% of the contract value shall be released to the concerned contractor. The allotted work shall be completed by the Contractor within sixty days from the date of receiving the work order failing which a penalty of Rs. 300/- (Rupees Three hundred only) per day shall be imposed on the defaulter contractor which will be recovered from his final bill, and in no case the delay to finish the contract job should not exceed sixty days. In case the excess delay, the concerned college committee may forfeit the Security Money deposited and/or make further deductions at any rate at its own discretion from the Final Bill which shall be final and binding on the concerned Contractor(s).

PRINCIPAL

Schedules of Items:

Sl. No.	Item Code	Item	Qty	UNIT	Rate	Amount
1	6.4.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : 6.4.1 Cement mortar 1:4 (1 cement : 4 coarse sand)	1.5	cum		
2	4.2.3	1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size	0.75	cum		
3	8.2.2.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. (Area of slab over 0.50 sqm)	5.4	sqm		
4	10.28	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	70	kg		
5	13.2.1	15 mm cement plaster on the rough side of single or half brick wall of mix : 13.2.1 1:4 (1 cement: 4 fine sand)	10	Sq.mtr		
6	MR	Dismantling of plaster/brick work of store room, making opening of door and re-fixing the existing door including repair and painting work after repair	one job	LS		
7	MR	Providing and fixing S.S. fastner 10mmX100mm.	30	each		
8	MR	Material and labour for burning of granite stone to prevent slippery on ramp.	58	Sq.ft.		
9	MR	Dismantling of existing marble stone flooring including removing the mulba upto 50mtr distance.	one job	LS		
					Total	

					Amount	

Name and Sign. Of Contractor_____

Address_____

Phone/Mobile Nos._____

GST No. ._____