

**DAULAT RAM COLLEGE HOSTEL**  
**UNIVERSITY OF DELHI**

DRCH/2024/11

Dated:26/07/2024

**NOTICE INVITING QUOTATION**  
**(CIVIL WORK)**

**Sealed Quotations are hereby invited from experienced contractors for the repair work of Booster pump House in the College Hostel.**

Sealed quotations for the above mentioned civil work, address to the undersigned should be dropped into the sealed box for receiving the quotations kept at Dispatch Section, in the College Hostel Administration office of this college on any working day till 02nd August 2024 during Office Hours (9:00 am – 5:00 pm). The sealed box containing sealed quotations and the sealed quotations shall be opened in the presence of the persons offering the said quotations and / or their representatives and the members of the concerned committee of this college at 11.00am on 05<sup>th</sup> August, 2024 in the Hostel Office.

Normally, the lowest quotations will be eligible for award of the job contracts but the concerned College committee reserves the right to award the job contracts to nearer higher-value quotations at its own discretion.

A security money deposit of Rs.10,000/- (Rupees Ten thousand only) for job contract shall have to be deposited to the undersigned after award of the work, which will be refunded on satisfactory completion of the job contracts.

On completion of 50% of the job within 30 days from the date of the work order received by the concerned contractor, a payment of 50% of the contract value shall be released to the concerned contractor. The allotted work shall be completed by the Contractor within sixty days from the date of receiving the work order failing which a Penalty of Rs. 300/- (Rupees Three hundred only) per day shall be imposed on the defaulter contractor which will be recovered from his final bill, and in no case the delay to finish the contract job should not exceed sixty days. In case the excess delay, the concerned college committee may forfeit the security money deposited and/or make further deductions at any rate at its own discretion from the Final Bill which shall be final and binding on the concerned Contractor(s).

**PRINCIPAL**

**Schedule of Items:**

S. No.	Item	Qty	UNIT	Rate	Amount
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the outside the college premises.	85	Sqft		
2	Repair to plaster of thickness 12mm to 20mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete as per the directions of Engineer-in-site.	990	Sqft		
3	Providing and fixing BRC nail of size 75x75x3 mm with fastener & wire to existing ceiling all as directed.	85	Sqft		
4	CEILING CEMENT PLASTER (IN FINE SAND) 12 mm cement plaster of mix 1:4 (1 cement: 4 fine sand)	85	Sqft		
5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	1075	Sqft		
6	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade 1 New work (two or more coats) over and including water thinkable priming coat with cement primer	485	Sqft		
7	External wall finished with acrylic smooth external paint with required shade two or more coat	590	Sqft		
8	Water proofing treatment on roof terrace by applying cement slurry mixed with water proofing cement compound and fiber glass cloth thereon, third layer with cement slurry mixed with water proofing cement compound and forth layer of brick tiling with cement mortar.	100	Sqft		
9	Repair work of two iron framed widow including glass work (including painting)	2	LS		
10	Repair work of iron framed door (including painting)	one job	LS		

Name and Sign. Of Contractor \_\_\_\_\_

Address \_\_\_\_\_

Phone/Mobile Nos. \_\_\_\_\_

GST No. . \_\_\_\_\_