

**DAULAT RAM COLLEGE HOSTEL**  
**UNIVERSITY OF DELHI, DELHI**

DRCH/01(Q)/2025/20

01/12/2025

**NOTICE INVITING QUOTATION**  
**(CIVIL WORK)**

**Sealed Quotations are hereby invited from experienced contractors for the Decorative DRCH Iron Letter Framed Structure Work in front lawn of College Hostel.**

Sealed quotations for the above mentioned civil work, address to the undersigned should be dropped into the sealed box for receiving the quotations kept at Dispatch Section, in the College Hostel Administration office of this College on any working day till 07<sup>th</sup> December 2025 during Office Hours (9:00 am – 5:00 pm). The sealed box containing sealed quotations and the sealed quotations shall be opened in the presence of the persons offering the said quotations and / or their representatives and the members of the concerned committee of this College at 2:30 pm on 08<sup>th</sup> December 2025 in the Hostel Office.

Normally, the lowest quotation will be eligible for award of the job contract but the concerned college committee reserves the right to award the job contract to nearer higher-value quotation at its own discretion.

The allotted work shall be completed by the contractor within thirty days from the date of receiving the work order failing which a penalty of Rs. 300/- (Rupees Three hundred only) per day shall be imposed on the defaulter.

Sd/-  
Principal  
Daulat Ram College  
University of Delhi

**DAULAT RAM COLLEGE HOSTEL**  
(UNIVERSITY OF DELHI)

Name of Work: **DECORATIVE DRCH IRON FRAMED STRUCTURE**

**SCHEDULE OF ITEMS**

S.no	Description of Work	Quantity/Unit	Rate	Amount
1	Earthwork excavation by mechanical/manual, including dressing of sides and ramming of bottoms, lifting up to 1.0 m including getting out the excavated soil & disposal of surplus excavated soil as directed, within a lead of 50 m all kinds of soil.	6.6 Cum		
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in the brick wall up to 0.75 m above ground level in all shapes and sizes in Cement mortar 1:4 (1 cement : 4 coarse sand)	3.15 Cum		
3	Cement Plaster (In Fine Sand) 12 mm cement plaster of mix (1 cement: 4 fine sand)	13.25 Sqm		
4	Providing and laying damp-proof course 50 mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	4.5 Sqm		
5	Providing base concrete work (1:2:4) for support alphabet (3'x 5' size) 4 Nos.	1.71 Cum		
6	Providing and fixing English Alphabet (DRCH) 3'x5' size with 12 mm diameter bars, covered with 1"x1"(10 Gauge) Jali and appropriate weather painted.	4 Nos		
	Total			
	Grand Total			

Name and Signature of Contractor \_\_\_\_\_

Address \_\_\_\_\_

Phone/Mobile Nos. \_\_\_\_\_

GST No. \_\_\_\_\_