

DAULAT RAM COLLEGE HOSTEL
UNIVERSITY OF DELHI, DELHI

DRCH/01(Q)/2025/20


15/12/2025

REVISED NOTICE INVITING QUOTATION
(CIVIL WORK)

Sealed Quotations are hereby invited from experienced contractors for the Decorative DRCH Iron Letter Framed Structure Work in front lawn of College Hostel.

Sealed quotations for the above mentioned civil work, address to the undersigned should be dropped into the sealed box for receiving the quotations kept at Dispatch Section, in the College Hostel Administration office of this College on any working day till 22th December 2025 during Office Hours (9:00 am – 5:00 pm). The sealed box containing sealed quotations and the sealed quotations shall be opened in the presence of the persons offering the said quotations and / or their representatives and the members of the concerned committee of this College at 2:30 pm on 23th December 2025 in the Hostel Office.

The allotted work shall be completed by the contractor within thirty days from the date of receiving the work order failing which a penalty of Rs. 300/- (Rupees Three hundred only) per day shall be imposed on the defaulter.


PRINCIPAL

DAULAT RAM COLLEGE HOSTEL

(UNIVERSITY OF DELHI)

Name of Work: **DECORATIVE DRCH IRON FRAMED STRUCTURE**

SCHEDULE OF ITEMS

S.no	Description of Work	Quantity/Unit	Rate	Amount
1	Earthwork excavation by mechanical/manual, including dressing of sides and ramming of bottoms, lifting up to 1.0 m including getting out the excavated soil & disposal of surplus excavated soil as directed, within a lead of 50 m all kinds of soil.	9.60 Cum		
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in the brick wall up to 0.75 m above ground level in all shapes and sizes in Cement mortar 1:4 (1 cement : 4 coarse sand)	8.00 Cum		
3	Cement Plaster (In Fine Sand) 12 mm cement plaster of mix (1 cement: 4 fine sand)	20.67 Sqm		
4	Providing and laying damp-proof course 50 mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	7.73 sqft		
5	Providing base concrete work (1:2:4) for support alphabet (3'x 5' size) 4 Nos.	1.08 Cum		
6	Making and fixing English Alphabet (DRCH) Letter 3'x5' size with 12 mm diameter bars, covered with 1"x1" (10 Gauge) Jali and appropriate weather painted.	4 Nos		
6.1	Broken brick bats Outer Platform wall	1.17 Cum		
6.2	MS Steel Work	225.60 kg		
6.3	Providing and fixing of artificial creeper plant	1 L.S		
	Total			
	Gst			
	Grand Total			

Name and Signature of Contractor _____

Address _____

Phone/Mobile Nos. _____

GST No. _____

