

DRC / IGL / 2025 / 1250

**DAULAT RAM COLLEGE
UNIVERSITY OF DELHI**

Dated: 16-12-2025

NOTICE INVITING QUOTATION

Sealed Quotations for the N.H.E lab P.N.G Pipeline Work as per IGL Norms, address to the undersigned should be dropped into the Sealed Box for receiving the Quotations kept at Dispatch Section, in the Administration office of this College on any working day till 24TH December, 2025 during Office Hours (9.am – 5.0pm).

On completion of 100% of the Job within 15 days from the date of the WORK ORDER received by the concerned Contractor, The allotted work shall be completed by the Contractor within 15 days from the date of receiving the WORK ORDER failing which a Penalty of Rs.300/- (Rupees Three hundred only) per day shall be imposed on the defaulter Contractor which will be recovered from his final bill, and in no case the delay to finish the Contract Job should not exceed 15 days. In case the excess delay, the concerned College Committee may forfeit the Security Money deposited if any and/or make further deductions at any rate at its own discretion from the Final Bill which shall be final and binding on the concerned Contractor(s).

SL No	Item description	Unit	Rate	Amount in Rs.
1.	M.S. Pipe 25mm (Make Jindal) I.G.L. Approved (including testing Certificates.	122 feet		
2.	Main control isolation ball valve 25mm (I.G.L. Approved including testing Certificates)	04 pcs.		
3.	Super Suraksha connection pipe (I.S.I & I.G.L. Approved) line to burner	06 pcs.		
4.	Short bend 25mm (I.B.R. tested with Testing certificate & I.G.L. approved)	20 pcs.		
5.	T- 25mm (I.B.R. tested with Testing certificate & I.G.L. approved	02 pcs.		
6.	Pipe stop plug 25mm I.B.R tested.	02 pcs.		
7.	Cim point valve burner (ON OFF Valve) I.G.L. approved (3/8 X3/8 size) CU Brass Heavy Make	06 pcs.		
8.	Brass Coupling Adopter (HEX) 3/8 size	06 pcs.		
9.	Point socket I.B.R. tested	08 pcs.		
10.	Complete gas line presser testing	122 feet		
11.	Bullnose coupler set (old gas line to new gas line connector set) IGL Approved	01 set.		
12.	Socket hex 25mm X 25mm (coupling)	01 set.		
13.	M.S. Angle clamp 25mm size (including fastener, PVC Pipe, U clamp complete set).	28 pcs.		
14.	Cartage . all gas line complete paint (two coat) all gas line fitting complete installation labour charge	One job (L/S)		
15.	3 rd party Inspection Charges	One Job		
	Total			

Sanjay B.
Principal
Daulat Ram College
University of Delhi
Maurice Nagar, Delhi-7
Sun